

dBF Associates, Architects

**HBH LAKEVIEW ICF
Lynchburg, Virginia
October 11, 2018**

ADDENDUM #3

TO: Contractors and all others to whom Drawings and Specifications have been issued.

The Contract Documents for the project consisting of Drawings and Specifications dated September 17, 2018, Addendum #1 dated October 4, 2018 and Addendum #2 dated October 8, 2018 shall be modified as follows:

- 1) Sheet SP2 – Refer to Attachment ‘A’ for additional information on the domestic water line and sprinkler line layouts. This information includes 3-page Detail 26.19B (Reduced Pressure Principle Backflow Prevention Assembly – 5/8” to 2” meters), 3-page Detail 26.20B (RPDA – For Independent Fire Service or Private Hydrant Installation with Domestic and Irrigation Services – disregard the Irrigation Service information), and the 5-page Detail 26.21 (Compound Meter Vault w/Separate Fire Line and Irrigation Service – disregard the Irrigation Service information). These are the details that the City of Lynchburg Department of Water Resources have confirmed are applicable to our project. The Schematic layout on Sheet SP2 shall be revised to reflect flipping the water line locations, so that the meter vault is on the domestic line. The RPZ with hot box shall remain on the domestic line, and the sprinkler line shall have the RPDA in a separate hot box. The City of Lynchburg shall make the actual tap off the existing 6” water line.
- 2) Sheet A8, Detail 3 Add Alternate #2 – Provide two (2) 4” diameter pipes. These shall be located in the chase area beside BR #3 Closet and in the 5 ½” wall between Room 107 Laundry and Room 110 Storage.
- 3) Specification Section 08700, 2.2.D.1.b – Delete reference to mortise locks.
- 4) Addendum #1, Item 16 – Revise Note 7 to read “Provide (2) 20A circuits for power to the domestic line RPZ hot box heater and to the sprinkler line RPDA hot box heater.